



**26 Ft Mobile Veterinary Unit
For Street Dogs AZ (Dr. Betsy Hershey)**

NEW 2019 Ford E450

Standard Vehicle Equipment:

- Ford E450 (Gasoline)
- 6.8L EFI V10 Gasoline Engine
- 5 Speed with Automatic Overdrive Transmission
- Power Windows & Locks with Remote
- 4 Wheel Anti-Lock Disc Brakes
- Power Steering with Tilt
- 55 gal. Fuel Tank
- Intermittent Windshield Wipers
- Alternator— 155 Amp
- Air Conditioner & Heat (In Cab Area)
- Exterior Color - Ford Oxford White
- Captains Chairs (Driver & Passenger) Faux Leather or Cloth
- AM/FM CD Radio with MP3 Input
- Drivers and Passengers Air Bags
- Full Ford Warranty
- Tires/Wheels 16"
- Stainless Steel Wheel Simulators
- Includes 2 Sets of Keys with Remote Entry for cab doors
- Back Up Camera—7" Flat Screen Video & Sound**

Warranty (Standard Ford Warranty applies)

- Bumper to Bumper..... 36 month/36,000 mileage
- Powertrain.....5yr /60,000 mileage
- Roadside Assistance5yr/60,000 mileage

Standard Mobile Clinic Box Structure:

FLOOR: FLAT FLOOR
I-BEAM X-MEMBER ON 16" CENTERS
UNDERCOATING
FLOOR 1-1/8" LAMINATED HARDWOOD
FILL SCREW HOLES AND SAND FLOOR
LINING ON WALLS: 1/4" plywood with Fiberglass covering – Seem less – White
LINING ON CEILING: 1/4" plywood with Fiberglass covering – Seem less – White
2" POLY SIDE WALL INSULATION (approx. 3" Wall Thickness)
1 3/4" POLY CEILING INSULATION (approx. 2.25" Ceiling Thickness)
PASS THRU TO CAB WITH SLIDING/LOCKING DOOR
FRONT END: 1/2" CORE FRP FRONT WALL
COMPOSITE CORNER WIND DEFLECTOR
ALUM. EXTRUDED FRONT CORNERS
WIND DEFL RAD .050 ALUM SMOOTH
SIDEWALLS: 1/2" GELCOAT WHITE EXTERIOR
SIDE WALL Z-POSTS ON 16" CENTERS
Z-POSTS ON FRONT WALL
ROOF: .040 ALUM ROOF SKIN
ANTI SNAG ROOF BOWS ON 16" CENTER
2 ROOF REINFORCEMENTS FOR A/C CUT (2) 14" X 14" HOLES FOR ROOF A/C UNITS.
LOCATED AT FRONT AND AT THE REAR OF THE ROOF.
EXTERIOR LIGHTS: STD SEALED SYSTEM MODEL 21 LED CLEARANCE LIGHTS
EXISTING TAILLIGHTS MOUNTED
BUMPER MEDIUM DUTY FULL WIDTH, 12G TREADPLATE STEEL
TURN HANDLE WITH KEY LOCK AND INTERIOR LOCK OF SIDE SLIDING ENTRY DOOR.
ONE 30" WIDE ENTRY SWING DOOR WITH 12" X 17" DARK TINT FIXED WINDOW WITH DOUBLE STEP STEPWELL
MUDFLAPS STD
MIRRORS - BLACK
EXTERIOR PAINT & COLOR: WHITE

Standard Clinic Equipment:

7 Kw ONAN Commercial EFI Gasoline Generator with Remote Start
Commercial Flooring with 1 1/2" Foundation – Brown
Lighting - 8 Interior LED Bulb Fixtures
Exterior Lighting over Entry Door
30" Entry/Exit Swing Door with Window, Grab Handle, & Lock (2 sets of keys)
Pass Thru to Cab with Locking Door—Stand Up
Exam Table Area
1 Surgery Table with Flat Top, Hydraulic Lift, & Tilt (VSSI)
2 Air Conditioners 15,000 BTU with Individual Thermostat Control
50 Amp Landline
15 Amp Charger
AGM Aux. Battery (79 Amp Hr)
Auto Transfer Switch (50 Amp)
Cages, Cabinetry, and Storage Built to Floor plan
Refrigerator— DC
Countertops – Faux Granite Look
Interior laminate for cages, interior walls, cabinets – Color to be Beige/Tan
110 Outlets on Interior (Built to Floor Plan)
Fire Extinguisher
Carbon Monoxide Detector
84 Inch Interior Height
5 YEAR Warranty from Magnum Mobile
Operating, Service, & Owners Manuals from Ford, ONAN, and Magnum. (And many other smaller manuals. (Ex. Awning, Water Pump, Heaters, etc)

26 Ft Mobile Spay-Neuter Unit (2019) Cost 135,500

Options Included:

Anesthesia Machine with Vaporizer – Smith’s (ISO) Package 4,650 ea.	9,300
Active Gas System- Smith’s - for two machines	950
Oxygen Concentrator (Philips 5 LPM for 2 Anes Mach)	2,500
Surgery Light – LED Flexible Arm with Triple Head	2,250
Digital Pullout Scale (Tree 700 lb)	850
Automatic Awning 16 Ft (Color –TBD)	2,950
Exam Table Upgrade to 5” Deep S/S Sink with grate and faucet sprayer	2,450
Hot Water Tank 2.5 Gallon with outlet	750
Two Electric Wall Heaters (750 ea)	1,500
Exam Light LED Flexible Arm	850
Central Shop Vacuum	850
X-Ray machine Sliding holder bracket above exam table with dedicated outlet	2,350
Dental Machine with Tankless Compressor – ENGLER – Scale-Aire	4,395
Exterior Graphics (Budgetted Amount - both sides, rear, above cab, lower cab doors	4,950
Picked Up at Magnum Mobile Factory (Includes Training)	N/C
Install of clients equipment at \$125/hr plus bracket costs	TBD

Options Included ADD: 36,895
Sub-Total Amount \$172,395
Arizona Tax (8.6%) 14,826
Total Amount \$187,221

- Training to be done at Magnum Factory during factory visit, on phone, or Facetime
- Build time approximate 3-4 months from receiving your Signed Contract.
- 35% Progress Payment paid with Signed Contract, 2nd Progress Payment of 35% Due on notice of Ford Chassis and exterior box is received at Magnum factory. The balance 30% is due when the Mobile Unit is complete but before Pick Up or Delivery is scheduled.
- AZ Taxes required to be paid, if client picks up at Factory or are in Arizona.
- Approx. Milelage of vehicle will be about 400 miles before pick up
- Quote good for 30 Days. (As of 11-20-19)